



ISPE®

Delaware Valley
Chapter

January 2017 Program

Case Study - New High Purity Water
System Technologies Deliver
Reliability & Sustainability for GSK

hargrove
engineers+constructors
controls+automation
life sciences



PRESENTERS



BRIAN LIPKO, PE

Senior Project Manager
Hargrove Life Sciences



BRIAN TERMINE, PE

Maintenance Engineering Manager
GlaxoSmithKline



STEVE WALTER, CPIP

Process Systems Technology Specialist
Hargrove Life Sciences

ACKNOWLEDGMENTS

RANDY MINTO, PE, Program Manager, GlaxoSmithKline

DAN D'AQUILA, PE, Director of Engineering & Validation, GlaxoSmithKline

ED STEVENS, Engineering Manager, GlaxoSmithKline


ALEX TANJUTCO, Validation Project Manager, GlaxoSmithKline

TED DOMBROWSKI, Senior Project Engineer, Arcadis (on behalf of GSK)

ROBERT HOEPPNER, Project Executive, Henderson Constructors, Inc.

MIKE BILLUPS, Project Manager, Henderson Constructors, Inc.

AGENDA



Introduction

Background
Objectives
Challenges



Execution

Design
Construction
Qualification



Results

Benefits
Lessons Learned
Summary

INTRODUCTION



Introduction

Background
Objectives
Challenges



Execution

Design
Construction
Qualification



Results

Benefits
Lessons Learned
Summary

INTRODUCTION: BACKGROUND



**CTM
(Clinical Trial Materials)
Facility**

**Manufactures purified
drug substances for
clinical trials worldwide**

INTRODUCTION: BACKGROUND

**Insufficient
Capacity for Future
Expansion or
Production
Increase**

**Parts no longer
Available**

**Existing HPW &
WFI Systems
Obsolete**

**Costly Systems
Not Energy
Efficient**

**Increased
Plant downtime Risk
due to insufficient
equipment
reliability**

INTRODUCTION: BACKGROUND

Project Scope

Replace 2 Obsolete Water Systems

HPW

High Purity Water

- New Reliable System Design
- Supply HPW to Biopharm Development Pilot Plant

WFI

Water for Injection

- Change System Configuration from 3 to 2 Pumps
- Replace WFI Control Panel
- Install Redundant VC Stills

INTRODUCTION: OBJECTIVES

**PROVIDE RELIABILITY THROUGH
REDUNDANCY**

DELIVER SUSTAINABILITY

**REDUCE WATER &
ENERGY USAGE**

**INCREASE SUPPLY
&
STORAGE CAPACITY**

**REPLACE
OBSOLETE EQUIPMENT**

**NO IMPACT TO
ON-GOING OPERATIONS**



INTRODUCTION: OBJECTIVES

RELIABILITY THROUGH REDUNDANCY

HPW

- Multi-Media Filters
- Softeners
- Carbon Filters
- RO/CDI Skid
- Tank Nitrogen Filters
- Distribution Pumps

WFI

- Vapor Compression Stills
- Tank Vent Filters
- Distribution Pumps

re·dun·dant

servicing as a duplicate for preventing failure of an entire system

No Unplanned Downtime

INTRODUCTION: OBJECTIVES

INCREASE SUPPLY & STORAGE CAPACITY

CLINICAL TRIALS

Need to be Adept & Flexible

Accommodate Emerging Technologies in Manufacturing

HPW

Generation and Storage Capacity

Insufficient during Maintenance Activities

WFI

Generation Capacity Bottlenecked

Required Daily Water Usage Planning Activities

INTRODUCTION: OBJECTIVES

OBSOLETE EQUIPMENT



Reverse Osmosis
Pre-Treatment System
(Built c.1987)



FRP High Purity
Water Storage Tank
2000 Gallon (Built c.1987)

INTRODUCTION: OBJECTIVES

OBSOLETE EQUIPMENT



Multi-Effect
WFI Still (5 MEF)
(Built c. 1987)



(3) WFI Distribution Pumps
One pump on each floor
(Spares in Warehouse)

INTRODUCTION: OBJECTIVES

OBSOLETE EQUIPMENT



Softener
Regeneration
Brine Tank



Softener Regeneration
Salt Pellets
Palletized 40 lb bags
Consumed 400-800 lb/day

INTRODUCTION: OBJECTIVES

NO IMPACT TO ON-GOING OPERATIONS

Building 38

Biopharm GMP
Clinical Trial
Production
Manufacturing

Building 5

Biopharm
Development
Pilot Plant

Building 4

Safety
Assessment
Manufacturing

INTRODUCTION: CHALLENGES

LIMITED
SPACE

IMPACT TO
ON-GOING
OPERATIONS:
PHASED
APPROACH

VENDOR
COMMITMENT
FOR
EQUIPMENT
DELIVERY

INSTALL
WINDOW
&
AVAILABLE
DOWNTIME

WFI
CONTROL
PANEL
CHANGE
OUT


INTRODUCTION: CHALLENGES

**BUILDING
38**
EXISTING
MECHANICAL
ROOM

Generation
Equipment

Utilities

Access



EXECUTION



Introduction

Background
Objectives
Challenges



Execution


Design
Construction
Qualification



Results

Benefits
Lessons Learned
Summary


EXECUTION: DESIGN




EXECUTION: DESIGN

Other Site Tours (Gemba)

Site 1:
Christ System



Site 2:
Siemens: PreVUE®



EXECUTION: DESIGN

EQUIPMENT EVALUATION

	Options	Decision
HPW	Single Pass vs. Double Pass RO	Single Pass
	Polisher vs. None	Install Polisher
	Carbon vs. Bi-sulfite vs. UV Light Filtration	Carbon Filtration
	Service Type vs. Back Washable Carbon Filters	Back Washable
	Hot Water vs. Chemical Sanitization	Hot Water Sanitization
	FRP vs. SS HPW Storage Tank	SS Tank
	High Recovery RO vs. None	High Recovery RO
	Nitrogen Blanket on Storage Tank vs. None	Nitrogen Blanket
	Bulk Brine vs. Day Tank	Both
	Redundant vs. Single Storage Tank Filters	Redundant Filters

EXECUTION: DESIGN

EQUIPMENT EVALUATION

	Options	Decision
WFI	Vapor Compression vs. Multi Effect	Vapor Compression
	Separate Pump per Floor vs. Redundant Pumps	Redundant Pumps
	Redundant vs. Single Storage Tank Filters	Redundant Filters

EXECUTION: DESIGN

SUSTAINABILITY EVALUATION

Equipment Costs, estimated:

Pretreatment Equipment
 WFI Still
 Total Equipment Cost

Single Pass RO	Single Pass RO with CDI	Double Pass RO	Double Pass RO with CDI	SPRO/DI followed by VC stills
\$800,000	\$1,150,000	\$1,200,000	\$1,400,000	\$804,000
\$535,000	\$535,000	\$535,000	\$535,000	\$1,071,000
		\$1,735,000	\$1,935,000	\$1,875,000

Operating Costs per day, estimated:

- **Standard Operation** with recirc and hot water sanitization
 Modified Standard Operation (note 5)
- **Start/Stop Operation** (Siemens S-3)
- **Christ Aqua Standard Operation** with high recovery, idle turndown and hot water sanitization
- **RO/DI with VC Stills** (note 6)
- **VC Still**

Systems Design Evaluations

Wastewater Volume Reduction

Wastewater Volume, gal/day:

- **Standard Operation** with hot water sanitization
 Modified Standard Operation (note 5)
- **Start/Stop Operation** (Siemens S-3)
- **Christ Aqua Standard Operation** with high recovery, turndown and hot water sanitization
- **RO/DI with VC Stills** (note 6)
- **VC Still**

Operating Cost Comparisons

12,624 gals	13,299 gals	12,000 gals	14,000 gals	\$1020
12,624 gals	13,299 gals	12,000 gals	14,000 gals	
16,198 gals	16,900 gals	16,000 gals	18,000 gals	
	9,975 gals			
3,120 gals	2,200 gals			300 gals

Limitations

activity / short life of polishing bed / pH adjust necessary to eliminate ammonia

resistivity necessary to eliminate ammonia

water quality higher than needed for WDI


EXECUTION: DESIGN

PROJECT LOCATIONS & CONSTRAINTS

Project Locations
Limited

***Only Feasible
Solution:***

Utilize existing
Courtyard
between B5 & B38
(14' W x 110' L)



EXECUTION: DESIGN

PROJECT LOCATIONS & CONSTRAINTS




Top of Courtyard
Looking NORTH



Bottom of Courtyard
Looking SOUTH


EXECUTION: DESIGN

2-Story Mechanical Room Design



EXECUTION: DESIGN

2-Story Mechanical Room Design



EXECUTION: DESIGN

NO IMPACT TO ON-GOING OPERATIONS

PHASE 1

Construct
Addition
&
Install
HPW
System

PHASE 1A

Install WFI
Pumps
&
Control
Panel

PHASE 2

Demo Old
HPW
System

Install WFI
VC Stills

Demo Old
Still

Phased
Construction/
Qualification
Approach

EXECUTION: DESIGN


PHASE 1

Construct 2-Story Addition for HPW

Between 2 Buildings

Adjacent GMP Operations

Limited Access



EXECUTION: DESIGN


PHASE 1

Construct 2-Story Addition for HPW

Between 2 Buildings

Adjacent GMP Operations

Limited Access



EXECUTION: DESIGN

SYSTEM CONSIDERATIONS

Energy Efficiency

S3 Technology
& Pump VFDs

Reduce Water
Usage

S3 Technology &
High Recovery RO

Bulk Brine
Tank System

WFI: Pump Schemes

Fathom Software

Complexity of Flows – Multiple Floors

Online TOC,
Conductivity &
Microbial Detection


Choose Vendor that Supplies Customizable PLC Controllers:

- Normalized Differential Pressure to determine cleaning interval
- Softener Regeneration is based on Hardness
- Softener Regeneration Rinse is based on Conductivity

EXECUTION: DESIGN

PHASE 1A - WFI

OLD SYSTEM



No Redundancy

Difficult to
Control Flow


Maintenance
requires Shutdown

Single Pump affected
Tank Temp and other
Floor Availability

EXECUTION: DESIGN

PHASE 1A - WFI

NEW SYSTEM



Generated from
Fathom Modeling

- Redundancy
- Control From Worst Case
- Pump Maintenance = No downtime
- VFD's to manage fluctuations
- Individual Loops can be Isolated

EXECUTION: DESIGN

WFI CONTROL PANEL



Extensive
Pre-Planning

Instruments = 86
I/O Points = 106

EXECUTION: DESIGN

HPW GENERATION SUMMARY

LATEST TECHNOLOGY

WATER & ENERGY EFFICIENT


AUTOMATED: SANITIZATION CYCLE

SEQUENCED CHANGE OVER

ALWAYS ONLINE

EXECUTION: CONSTRUCTION

TIMELINE



EXECUTION: CONSTRUCTION



Existing
Courtyard

PHASE 1



Stone & Soil
Excavation

1st Floor Slab
Installation



EXECUTION: CONSTRUCTION

TEMPORARY PROTECTIONS

Maintain Building Integrity during Removal of Building Façade



Removal of the façade exposed
Utilities above occupied space inside



Installed Temporary Partition Walls in
Active Areas & Issued Change Control

Updated Qualified Flow Drawings Continually During Construction

EXECUTION: CONSTRUCTION

PHASE 1



Building Structure
Construction



Large Crane due to
Limited Access

EXECUTION: CONSTRUCTION

PHASE 1



Installation of
HPW Equipment



EXECUTION: CONSTRUCTION

PHASE 1



Outdoor Bulk Brine Tank



2nd Floor HPW

EXECUTION: CONSTRUCTION

PHASE 1



1st Floor
Dual RO Skids



1st Floor
HPW Tanks & Pumps

EXECUTION: CONSTRUCTION

PHASE 1



2nd Floor Dual Softeners
& Multi-Media Filters



2nd Floor
Dual Carbon Filters

EXECUTION: CONSTRUCTION

PHASE 1A



B38 Mechanical Room
Existing WFI Pumps to Demo



B38 Mechanical Room
New WFI Pumps

EXECUTION: CONSTRUCTION

PHASE 2



B38 Mechanical Room
HPW System to Demo



Access Doors to B38
Mechanical Room

EXECUTION: CONSTRUCTION

PHASE 2



New WFI Stills at FAT
Sugarland, TX




New WFI Stills in
B38 Mechanical Room

EXECUTION: CONSTRUCTION

LEVERAGED QUALIFICATION APPROACH

Vendor Qualification Documents Reformatted to GSK Standards PRIOR to Factory Acceptance Test (FAT)



EXECUTION: CHALLENGES

CONSTRUCTION

Constrained Area within the
Middle of Operating Buildings

S3 Design
Not Turn-Key

Polisher Tank
Delivery

Sartorius Filter
Housings

Delivery of
High Purity Equipment

Installation of
High Purity Equipment

DI Tank
Filters

Failure of PQ1
Testing (Plan B)

EXECUTION: QUALIFICATION

VALIDATION DOCUMENTATION

EXTENSIVE DOCUMENT MANAGEMENT	1	Validation Master Plan (HPW/WFI) including 3 Validation Interim Reports
	5	User Requirement Specs
	14	Change Controls
	27	Installation Operation Qualification Documents
	10	Standard Operating Procedure Updates
	22	Functional Design Specifications
	3	Factory Acceptance Test / Site Acceptance Test
	2	Design Qualifications

RESULTS



Introduction

Background
Objectives
Challenges



Execution

Design
Construction
Qualification



Results

Benefits
Lessons Learned
Summary

RESULTS: BENEFITS



INCREASED
SUPPLY &
CAPACITY



IMPROVED
RELIABILITY
&
DELIVERED
SUSTAINABILITY



LOWER
OPERATING
EXPENSE

RESULTS: BENEFITS

IMPROVED SUPPLY TO CLINICAL OPERATIONS

Redundant HPW
& WFI

B38

B5

B4



Increased
Capacity &
Reliability



RESULTS: BENEFITS

Water Consumption

- Reduced ~**11,000** gallons per day / ~**4,050,000** gallons per year
- Cost savings of ~**\$32K** per year (Water & Sewer)
- Supports GSK's strategic goal to reduce Water Consumption

Electrical Energy

- Pumping operations reduced by 88%
- Cost Savings of ~**\$28k** per year

Carbon Emissions


- Annual carbon emissions reduction of **348 TONNES CO2**
- Supports GSK's strategic goal to reduce Carbon Footprint

Operations

- New System supplying HPW to Biopharm Development Pilot Plant
- Eliminated Resin Bed Train Service
- New Bulk Brine & Online Microbial Detection Systems
- Cost Savings of ~**\$170,000** per year

RESULTS: BENEFITS

Online Microbial
Detection System



Only 4th System Installed in US

FUTURE OPERATING SAVINGS

Reduces Regulatory
Sampling

Doesn't Eliminate

Bioburden/Endotoxin

20% (96)
Samples/
Year



RESULTS: LESSONS LEARNED

COULD HAVE DONE BETTER

Procurement
Management

WFI Batchers Orifices

WFI Still & Clean
Steam Supply Pressure

PQ1 Failure / 'Plan B'

WHAT WENT WELL

Full Control
Replacement:
Demo Simulation
of functionality

Integration of
Automation Contractor

Selection of
Construction Contractor

RESULTS: SUMMARY


SUCCESS!

**CONSTRUCTED
& VALIDATED
IN LESS THAN
1 YEAR**

**TWO
VALIDATED
SYSTEMS
& NEW
GENERATION
EQUIPMENT**

**MINIMAL
IMPACT TO
ON-GOING
OPERATIONS**

RESULTS: SUMMARY



RESULTS: SUMMARY

OBJECTIVES EXCEEDED!



We kept the Trains on the Tracks

QUESTIONS

